

The Contractor shall be aware that the excavation and fill quantities either shown on the plans or available in this office are based on the best information available.

The Engineer, however, takes no responsibility for shortages or excesses in fills or cut.

These quantities can vary based on the condition of the area, whether grassy or plowed, original moisture conditions at the time of the topographic survey, and moisture conditions during the course of construction. Either one or all of these conditions can greatly affect the quantities indicated.

- Walkways shall be scored into 4 foot sections unless otherwise specified.
- If extrusion machine is used, expansion joints shall be deep score 1/3 the thickness.
- KIOSK - Triangular Post and Panel - for installation see manufacturer specifications, G.S. Images, P.O. Box 1288 Hagerstown, MD 21741 or approved equal. PH (301) 791-6920.
- GAZEBO - Polygon Square Model SD 16 - For installation see manufacturer specifications, W. H. Porter Inc approved equal. PH (414) 344-1943.
- PEDESTRAIN RAMP - install per County of Sonoma Department of Public Works standard drawing No. SD-9 Pedestrian Ramp for the Handicapped.
- BENCH - (4) 6 ft. Park Bench item 6. Sonoma County Probation Camp or approved equal. To be provided by the County.
- PICNIC TABLE - (1) Item 1- 8' Picnic Table and (1) Item 3- 8' handicap picnic table, Sonoma County Probation Camp or approved equal. To be provided by the County.

- The finished asphalt concrete surface shall receive a fog seal of 1" asphaltic emulsion applied at 0.06 to 0.10 gallon per square foot. Asphaltic emulsion shall meet the applicable provisions of Section 94.1, "Asphalt Emulsions," of the Standard Specifications.
- The contract price paid per square yard of fog seal shall include compensation for furnishing all labor, materials, tools and equipment and doing all work involved in furnishing and placing fog seal as specified, together with traffic control.
- TREE WORK - Would be for trees that need pruning of root area excavation as needed to clear traffic areas. An arborist or certified tree worker would be needed for this work. See Technical Specification Section 02115 Tree Protection and Tree Work for information.
- Broken asphalt concrete may not be used as fill material.
- Saw cut and remove existing asphalt for new island constructed outside new island and patch.
- Remove and stockpile existing wheel stops.
- Move barriers at entry; relocate to trailer parking area to east of

IDENTIFICATION STAMP OF THE STATE ARCHITECT

APPLICATION NO.: _____
 A C _____ F L S _____ S S _____
 DATE: _____

Revisions

No.	Date	By	Description

Plans Approved By: _____
 Title: _____

Project
**CONCEPT PLAN
 WESTSIDE PARK**

Location
 BODEGA BAY
 SONOMA COUNTY


Designed RUDY OINEZA	Drawn
Checked	Check Date 6.5.2008

Sheet Title
CONCEPT PLAN

Date 6.5.2008	File Number XXX-1
Reference North	Sheet Scale 11x17: 1"=60' 22x34: 1"=30'
	Sheet Number 1
	1 of 1

PROPOSED IMPROVEMENTS

1 ENTRY FEE SIGN	6 3- FLOODLIGHTS WITH MOTION SENSORS
2 AESTHETICALLY IMPROVE FISH CLEANING STATION	7 WIDEN BOAT RAMP TO 3-LANES (45') REPLACE BOARDING FLOATS DREDGE FROM END OF RAMP TO GREEN BUOY
3 AUTOMATED ENTRY FEE PAY STATION	8 DECOMPOSED GRANITE WALKWAY AND CONCRETE PICNIC TABLES
4 -NOT USED-	9 CONCRETE PROJECT SIGN
5 BOAT WASHDOWN AREA (TIMED)	10 LARGER CONCRETE APRON



CONCRETE
 TREE TO BE REMOVED
 TREE TO REMAIN

FOR SECTIONS SEE SHEET 6

DRAINAGE / IMPROVEMENT